

Project Information:

Owner: Spirit in the Hills

Lutheran Church

Subdivision: Bee Creek Ranchettes

Section: One

Lot: 4

Travis County Transportation and Natural Resources has completed the review of the Spirit in the Hills site plan, Development Permit Number 19-25218, on November 3, 2021. In lieu of signature, this statement has been posted on the cover sheet at the request of the reviewer, John Ellis, P.E. of Travis County TNR Development Services. Any questions regarding the completed review by Travis County may be directed to John Ellis at John.Ellis@traviscountytx.gov.

Signature and Permit Block for Lower Colorado River Authority, Highland Lakes Watershed Ordinance

LCRA Date

Note submitted letter of no permit required by LCRA LCRA Case # 2020-3832, South, 02/12/20

Site Location




EXHIBIT 482.301B TRAVIS COUNTY STANDARD CONSTRUCTION NOTES FOR SITE DEVELOPMENT

- Each driveway must be constructed in accordance with Travis County Code Section 482.302(g), and each drainage structure or system must be constructed in accordance with the City of Austin Drainage Criteria Manual, unless other design criteria are approved by Travis County.
- Before beginning any construction, the owner must obtain a Travis County development permit and post the development permit, the TCEQ Site Notice, and any other required permits at the job site.
- Construction may not take place within Travis County right-of-way until after the owner has submitted a traffic control plan to Travis County and obtained written approval of the traffic control plan from Travis County.
- The contractor and primary operator shall follow the sequence of construction and the SWP3 in these approved plans. The contractor and primary operator shall request Travis County inspection at specific milestones in the sequence of the construction of the site development corresponding to the priority inspections specified in Construction Sequencing notes in these approved plans. Development outside the limits of construction specified in the approved permit and construction plans is prohibited.
- Before beginning any construction, all Storm Water Pollution Prevention Plan (SWP3) requirements shall be met, and the first phase of the temporary erosion control (ESC) plan installed with a SWP3 Inspection Report uploaded to mypermitnow.org. All SWP3 and ESC Plan measures and primary operator SWP3 inspections must be performed by the primary operator in accordance with the approved plans and SWP3 and ESC Plan Notes throughout the construction process.
- Before starting construction, the owner or contractor or their designated representatives shall submit a request via the mypermitnow.org customer portal for Travis County to request and schedule a mandatory Preconstruction Conference and ESC Inspection. If further assistance is needed, the TNR Planning and Engineering Division staff or TNR Storm Water Management Program staff can be contacted by telephone at 512-854-9383.
- The contractor shall keep Travis County TNR assigned inspection staff current on the status of site development and utility construction. The contractor shall notify Travis County and request priority inspections through the mypermitnow.org customer portal for Travis County in accordance with the specific milestones in the Construction Sequencing notes in these approved plans. On the ground topographical survey completed on 02/07/20 by All Star Land Surveying
- Fill material must be managed and disposed of in accordance with all requirements specified in the approved plans, SWP3, and the Travis County Code. The contractor shall stockpile fill and construction materials only in the areas designated on the approved plans and not within the 0.2 percent annual chance floodplain or the 1 percent annual chance floodplain, waterway setback, Critical Environmental Feature setback, or outside the limits of construction. Disposal of solid waste materials, as defined by State law (e.g., litter, tires, decomposable wastes, etc.) is prohibited in permanent fill sites.
- Before disposing any excess fill material off-site, the contractor or primary operator must provide the County Inspector documentation that demonstrates that all required permits for the proposed disposal site location, including Travis County, TCEQ Notice, and other applicable development permits, have been obtained. The owner or primary operator must revise the SWP3 and ESC Plan if handling or placement of excess fill on the construction site is revised from the existing SWP3. If the fill disposal location is outside Travis County or does not require a development permit, the contractor or primary operator must provide the County Inspector the site address, contact information for the property owner of the fill
- The design engineer is responsible for the adequacy of the construction plans. In reviewing the construction plans, Travis County will rely upon the adequacy of the work of the design engineer.
- In the event of any conflicts between the content in the SWP3 Site Notebook and the content in the construction plans approved by Travis County, the construction plans shall take precedence.
- A minimum of two survey benchmarks shall be set, including description, location, and elevation; the benchmarks should be tied to a Travis County control benchmark when possible.
- Any existing pavement, curbs, sidewalks, or drainage structures within County right-of-way which are damaged, removed, or silted, will be repaired by the contractor at owner or contractor's expense before approval and acceptance of the construction by Travis County.
- Call the Texas Excavation Safety System at 8-1-1 at least 2 business days before beginning excavation activities.
- All storm sewer pipes shall be Class III RCP, unless otherwise noted.
- Contractor is required to obtain a utility installation permit in accordance with Travis County Code Section 482.901(a)(3) before any construction of utilities within any Travis County right-of-way.
- This project is located on Flood Insurance Rate Map 48453 CO 195H
- Temporary stabilization must be performed in all disturbed areas that have ceased construction activities for 14 days or longer, in accordance with the standards described in the SWP3 and ESC Plan Sheet Notes.
- Permanent site stabilization/re-vegetation must be performed immediately in all site areas which are at final plan grade and in all site areas specified in the approved plans for phased re-vegetation, in accordance with the standards described in the SWP3 and ESC Plan Sheet Notes.
- All trees within the right-of-way and drainage easements shall be saved or removed in accordance with the approved construction plans. Travis County tree preservation standards in Travis County Code Section 482.973, including installation and maintenance of all specified tree protection measures, must be followed during construction.
- An Engineer's Concurrence Letter in accordance with Travis County Code Section 482.953 must be submitted via the mypermitnow.org customer portal for Travis County when construction is substantially complete. The Engineer's Concurrence Letter must be submitted before the contractor or primary operator requests a final inspection by Travis County.
- Site improvements must be constructed in conformance with the engineer's construction plans approved by Travis County. Non-conformance with the approved plans will delay final inspection approval by the County until plan conformance is achieved or any required plan revisions are approved.
- Final Site Stabilization. All areas disturbed by the construction must be permanently revegetated and all temporary sediment controls and accumulated sedimentation must be removed before the County will issue a Certificate of Compliance for final site stabilization as part of final inspection and project completion. A Developers Contract, as described in the SWP3 and ESC Notes Sheet may be executed with Travis County for conditional acceptance of a project for which has ESC Fiscal Security posted and for which all items are complete

EXHIBIT 482.301G SEQUENCE OF CONSTRUCTION AND PRIORITY INSPECTIONS – SITE DEVELOPMENT

The owner and primary operator must follow this basic sequence of construction for each site development, inclusive of all non-residential site development projects. Within the following sequence of construction are listed Priority Inspections that the owner and primary operator must request from a representative of Travis County's Storm Water Management Program inspection team. Each Priority Inspection must be requested on-line through the mypermitnow.org customer portal for Travis County. The Priority Inspections in this exhibit are consistent with the priority inspections found in the customer portal for the project. For assurance purposes, a second request to Travis County is strongly encouraged by additionally sending an e-mail to env-inspect@traviscountytx.gov.

The sequence for items 1-4 and items 9-12 must not be altered, but the sequence for items 5-8 may be modified with the written approval of the County.

- ESC Installation. Install all temporary erosion and sediment controls (ESC) and tree protection measures in accordance with the approved ESC Plan sheets and the SWP3.
 - Have a qualified inspector (as specified in Section 482.934(c)(3) of the Travis County Code) inspect the temporary erosion and sediment controls and prepare a certified SWP3 Inspection Report regarding whether the temporary erosion and sediment controls were installed in conformance with the approved plans;
 - Upload the qualified inspector's certified SWP3 Inspection Report to the mypermitnow.org customer portal for Travis County; and
 - Request a mandatory pre-construction meeting with Travis County through the mypermitnow.org customer portal for Travis County giving at least 3 business days notification.
- Pre-construction Meeting and ESC Inspection. Hold a mandatory pre-construction meeting that addresses the items in EXHIBIT 482.950 and the ESC Pre-construction Inspection by the County and obtain County's approval to start construction. (PRIORITY INSPECTION)
- Inspect for Compliance with SWP3 and ESC Plan. Maintain and inspect the SWP3 controls and prepare and upload a weekly certified SWP3 Inspection Report that includes the contents listed in EXHIBIT 482.951 to the mypermitnow.org customer portal for Travis County.
- Construct Sediment Basin(s). Construct any storm water pond(s) first, whenever applicable, to be functional as construction sediment basin(s) before grading and excavating the entire site, as follows:
 - Clear, grub, and excavate only the site areas and cut and fill quantities necessary to construct the pond(s) in accordance with these approved plans and the minimum standards described in the SWP3 and ESC Plan Sheet Notes for the temporary sediment basin embankments, walls, inlets, outfalls, drainage conveyance measures, sediment controls, and stabilization.
 - Request County inspection and obtain County's written approval of the temporary sediment basin(s) before proceeding further in the sequence of construction. (PRIORITY INSPECTION)
- Construct Site Improvements. Begin the primary site clearing, excavation, and construction activities and continue the SWP3 and ESC Plan implementation and maintenance per the approved plans.
- Construct Driveway Approach and Right-of-way Improvements. Install driveway approach and drainage and road improvements in the County right-of-way per approved plans, when applicable. Request a County Pre-Pour Inspection of the driveway through the mypermitnow.org customer portal for Travis County giving at least 3 business days notification. (PRIORITY INSPECTION).
- Perform temporary stabilization in all disturbed areas that have ceased construction activities for 14 days or longer.
- Perform permanent site stabilization/re-vegetation immediately in all site areas at final plan grade and in all site areas specified for phased re-vegetation.
- Complete Permanent Water Quality Controls. Begin completion of permanent water quality control(s) and install the underdrain per approved plans, when applicable.
 - Remove construction sediment, re-establish the basin subgrade, and install underdrain piping.
 - Request County inspection and obtain County's written approval of the underdrain piping installation and associated construction materials (aggregate, filter media, etc.) before covering the underdrain and proceeding with construction of the control. (PRIORITY INSPECTION).
- Complete construction site improvements and final stabilization per the approved plans.
- Provide Engineer's Concurrence Letter through the mypermitnow.org customer portal for Travis County when construction is substantially complete and request a final inspection by Travis County. (PRIORITY INSPECTION)
- Obtain a Certificate of Compliance when all final inspection punch list items, including final site stabilization and removal of temporary sediment controls. If necessary, provide a Developers Contract to the County to request conditional acceptance for use or occupancy of the site with all items completed except re-vegetation growth coverage. Request a re-inspection when re-vegetation coverage is complete. (PRIORITY INSPECTION)

Before Project approval/issuance of the Certificate of Completion (CoC) and Fiscal Release the following must be complete:

- The owner must complete and submit a PWQC Permit Application to LCRA and a PWQC Maintenance Plan for review and approval. Both documents must be submitted and approved prior to the project Final Acceptance.
- Upon approval, the Maintenance Plan along with the original notarized document must be filed in the Real Property Records of Travis County. Proof of filing must be provided prior to the project Final Acceptance.
- The PWQC Maintenance Permit must be signed by the site owner and submitted to LCRA using their provided format.
- The PWQC Maintenance Plan must be sealed and signed by the design engineer.
- Upon request a PWQC Permit Application and/or a template for a PWQC Maintenance Plan will be provided or uploaded to the mypermitnow.org account.

Notes continued on next page

List of Drawings and Reports:

Pg.	Drwg No.	Title
1	01A	Cover Page
2	01B	Required Notes
3	02	Existing Conditions
4	03	Proposed Site Plan
5	04	Temporary Erosion and Sediment Control Plan
6	05	Creek Set Back Averaging Plan
7	06	Perm. Erosion, Sediment & Water Quality Plan
8	07	Restoration/Water Quality Details
9	08	Stabilization/Restoration Plan
10	09	Paving Details
11	10	Drainage Area Maps
12	11	Grading Plan
13	12	Culvert and Creek Sections
14	13	South Pond Details
15	14	North Pond Details
16	15	Traffic Control Plan
17	16	Septic System Modifications Plan
18	17	Driveway Exit Sightlines

Reports and Attachments

Response to 01/29/20 Comments
 Response to 02/14/20 Comments
 Response to 06/22/20 Comments – Engr
 Response to 11/05/20 Comments - Env
 Engineering Report dated 05/07/20 (sealed 05/08/20)
 ESC Fiscal Cost Estimate Dated 04/20
 Environmental Resource Inventory Dated 09/30/19
 Balcones Canyonlands Conservation Plan Letter Dated 8/26/19
 Phase I Environmental Site Assessment Dated 06/14/19
 SWP3 Dated 10/19/19
 Letter of no permit required from the LCRA dated 02/12/20
 Letter of no permit required from the USACE dated 03/20/20
 Copy of Permit from Travis County Fire Marshal
 Letter from T.C. Fire Marshal regarding combined building/site.
 Original Plat with various dates all 03 of 1970.
 Channel Flow Calculations
 Detention Basin/Pond Calculations
 Map Exhibits
 Copy of Permit for Septic System Modifications
 Traffic Impact Analysis dates 11/01/20

Schedule your projects pre-construction meeting through the mypermitnow.org account after the initial 3rd Party SWP3 inspection report has been uploaded and all permits and notices have been posted, then follow up with emails to the environmental inspector at env-inspection@traviscountytx.gov and the engineering inspector,

Johnny Anglin, at johnny.anglin@traviscountytx.gov

Total site area within the limits of construction: 2.9 Acres
 Total area of disturbance: 1.3 Acres
 Total area of new impervious cover: .98 Acres
 Name and Segment ID for downstream receiving waters:
 Un-named tributary" approximately 2,915' from the edge of the 100 year FEMA floodplain for Colorado River / Lake Travis

Engineer will make periodic inspections and reports of the site status and conditions during construction to ensure compliance with plans and to address any necessary structural compliance items.

All structural field changes require a plan revision approval in writing before commencement of the work.



The Engineer who prepared these plans is responsible for their adequacy. In approving these plans, Travis County must rely upon the adequacy of the work of the design engineer.

REV.	DESCRIPTION	DATE	BY
A	Added "In Lieu of Signature" statement by TC TNR	11/03/21	SLM

Lake Travis Engineering and Inspection LLC TBPE Firm No. 10248 / 512 633 7097	
2106 Bee Creek Rd. Cover Sheet – TC FD Submittal	
Scale: 1/4" = 1'-0"	DATE: 12/06/20
DRWG NO: 01A	REV: 1 OF 1

Project Information:


Owner: Spirit in the Hills
Lutheran Church
Subdivision: Bee Creek Ranchettes
Section: One
Lot: 4

Copy of Original Recorded Plan for Bee Creek Ranchettes

Vol. 49 Page 75
PLAT RECORD, TRAVIS COUNTY, TEXAS

26-8760

Vol. 49 Page 75
PLAT RECORD, TRAVIS COUNTY, TEXAS



BEE CREEK RANCHETTES SECTION ONE

SURVEYED BY: BRYANT-CURINGTON, INC.

THE STATE OF TEXAS COUNTY OF TRAVIS KNOW ALL MEN BY THESE PRESENTS...

THE STATE OF TEXAS COUNTY OF TRAVIS I, Max Emilia Limberg, Clerk of the County Court...

THE STATE OF TEXAS COUNTY OF TRAVIS I, Max Emilia Limberg, Clerk of the County Court...

BEFORE ME the undersigned authority on this day personally appeared Thomas R. Jones...

FILED FOR RECORD ON the 22nd day of March, A.D. 2010...

IN WITNESS WHEREOF, I have hereunto set my hand and seal of the County Court...




EXHIBIT 482.950

Pre-Construction Conference Planning and Agenda for SWP3 and ESC Plan

Before starting construction, the owner or their representative must submit a request, using the mypermitnow.org customer portal for Travis County...

After arranging an agreed upon date with the County and providing the initial SWP3 Inspection Report, the owner or owner's designated representative shall provide notice of the SWP3 pre-construction conference...

- 1. Designated County Inspector(s)
2. Design engineer for the approved plans and SWP3, or their representative
3. Contractor(s)/Primary Operator(s)
4. Primary Operator's qualified inspector responsible for preparing the SWP3 Inspection Reports
5. Other stakeholders, as appropriate: municipalities, utilities, etc.

The SWP3 pre-construction conference may be a standalone meeting or a part of a larger pre-construction conference, but must include an on-site inspection approval of the first phase of the project's ESC Plan by the County Inspector before construction begins.

- 1. The SWP3 Site Notebook for the project, including review of completeness, signatures, consistency with the approved construction and ESC plans...
2. The sequence of construction and ESC Plan implementation; sediment basin construction scope prior to full site grading...
3. Sediment controls; phasing of perimeter and interior sediment controls during construction...
4. Adequacy of the first ESC phase and future ESC phases to address specific site conditions...
5. Temporary and permanent stabilization and re-vegetation requirements...
6. On and off-site temporary and permanent spoil and fill disposal areas...
7. Permanent water quality controls construction and County inspections...
8. Supervision of the SWP3 implementation by the primary operator's designated project manager...
9. Inspection and preparation of the weekly SWP3 Inspection Reports...
10. Observation and documentation of existing site conditions adjacent to the limits of construction...
11. Special site conditions and plan provisions, such as protection of waterways...
12. Rain gage location or rainfall information source to be used during construction...
13. Final inspection and acceptance requirements...
14. Exchange of telephone numbers and contact information for the primary participants.

The design engineer shall prepare and distribute notes, key decisions, and follow up from the preconstruction conference to all participants within three business days after completion of the conference.

EXHIBIT 482.951 SWP3 Inspection Areas and Report Contents

The owner or primary operator of the construction site shall designate a qualified inspector possessing the required certification (as specified in Section 482.934(c)(3)) to perform a weekly SWP3 inspection and prepare a signed SWP3 Inspection Report of the inspection findings.

The construction site areas and the control measures listed herein are to be used as a minimum as the uniform criteria by the owner's qualified inspector, as well as the County Inspector, to evaluate and determine a project's compliance status with the approved SWP3 and ESC Plan.

In addition, on an ongoing basis and following storm events, the primary operator's responsible on-site personnel shall also inspect and address these items during construction as required by the SWP3, ESC Plan, and Travis County Code, Section 482.951.

Areas of Inspection. At the very least, the following areas must be inspected:

- 1. Disturbed areas and the approved limits of construction.
2. Perimeter and interior sediment controls.
3. Areas undergoing temporary stabilization or permanent vegetation establishment.
4. Temporary and permanent fill and spoil storage or disposal areas.
5. Storage areas for materials and equipment that are exposed to rainfall.
6. Outfall locations and the areas immediately downstream.
7. Structural controls, including sediment ponds, sediment traps, and drainage diversions.
8. Haul roads and locations where vehicles enter or exit the site, and adjacent roadways for evidence of off-site sediment tracking.
9. Waterway crossings and areas adjacent to waterways and critical environmental features.
10. Concrete wash out areas and all areas requiring control measures for non-storm water discharges...
11. Locations of all control measures that require maintenance...
12. Locations of any discharge of sediment or other pollutants from the site...
13. Locations of control measures that failed to operate as designed...
14. Locations where an additional ESC or control measure is needed.


The SWP3 Inspection Report must include:

- A. Findings as to whether the following structural and non-structural controls required for the site areas listed above are functioning in compliance with the approved SWP3 and ESC Plan:
1. Erosion source controls...
2. Sediment controls...
3. Permanent erosion and soil stabilization controls...
4. Other applicable controls and pollution prevention measures.
B. Rainfall documentation:
1. For projects that comprise ten acres or more...
2. For projects that comprise less than ten acres...
C. Corrective actions required for any non-compliant items...

The SWP3 Inspection Report contents must contain the inspection findings for the required areas and control measures listed herein and certify whether the site is in compliance with the approved SWP3 and ESC Plan.

Either at the time of each SWP3 inspection, or no later than the date of the inspection, the owner's qualified inspector shall prepare and sign a SWP3 Inspection Report.

The owner or primary operator shall upload each required SWP3 or ESC Plan Inspection Report to the mypermitnow.org customer portal for Travis County. An alternate method of report submittal may be used if approved by the County Inspector.



The Engineer who prepared these plans is responsible for their adequacy. In approving these plans, Travis County must rely upon the adequacy of the work of the design engineer.







Table with columns: REV, DESCRIPTION, DATE, BY. Includes project details like 'Lake Travis Engineering and Inspection LLC', '2106 Bee Creek Rd.', and 'Required Notes - TC FD Submittal'.



Total Area = 4.82 Acres	209,959.2 S.F.
Impervious Cover	
Existing Roads	16,183.7 S.F.
Home	2,367.9 S.F.
Garage/Event Center	3,915.7 S.F.
Domestic Water Tank Pad	118.8 S.F.
Total Impervious Cover	22,586.1 S.F.
Impervious %	10.8%

Tree Information


5.	9" Live Oak
6.	6" Live Oak
7.	11" Live Oak
8.	12" Live Oak
9.	7" Hackberry
10.	27" Live Oak
11.	11" Live Oak
12.	6" Live Oak
13.	11 1/2" Hackberry





REV.	DESCRIPTION	DATE	BY
Lake Travis Engineering and Inspection LLC TBPE Firm No. 10248 / 512 633 7097 2106 Bee Creek Rd Existing Conditions			
Scale: 1" = 50'	SIZE: C	FSC/MNO	DWG NO: 02
Date: 05/08/20	SCALE	SHEET	REV: 2 OF 1

Total Area = 4.82 Acres	209,959.2 S.F.
Impervious Cover	37,892.6 S.F.
Driveways and Parking	2,367.9 S.F.
Office (Former House)	3,915.7 S.F.
Sanctuary/Fellowship Hall (Former Event Center)	4,550.0 S.F.
Future Sanctuary	400.0 S.F.
Fire Tank Pad	118.8 S.F.
Domestic Water Tank Pad	49,363.8 S.F.
Total Impervious Cover	23.5%





- Tree Information
5. 9" Live Oak
 6. 6" Live Oak
 7. 11" Live Oak
 8. 12" Live Oak
 9. 7" Hackberry
 10. 27" Live Oak
 11. 11" Live Oak
 12. 6" Live Oak
 13. 11 1/2" Hackberry
- CRZ
- 1/2 CRZ




Location of unnamed tributary on site with relationship to Colorado River/Lake Travis



Accessibility Ramp Detail



Each space to have signage indications accessible spaces.




REV.	DESCRIPTION	DATE	BY
	Lake Travis Engineering and Inspection LLC TBPE Firm No. 10248 / 512 633 7097		
	2106 Bee Creek Rd Proposed Site Plan		
	Scale: 1" = 30'	DWG NO: 03	REV:
	Date: 09/19/21	SHEET	1 OF 1




Total Area = 4.82 Acres	209,959.2 S.F.
Impervious Cover	
Driveways and Parking	37,892.6 S.F.
Office (Former House)	2,367.9 S.F.
Sanctuary/Fellowship Hall (Former Event Center)	3,915.7 S.F.
Future Sanctuary	4,550.0 S.F.
Fire Tank Pad	400.0 S.F.
Domestic Water Tank Pad	118.8 S.F.
Total Impervious Cover	49,363.8 S.F.
Impervious %	23.5%

Tree Information	
5.	9" Live Oak
6.	6" Live Oak
7.	11" Live Oak
8.	12" Live Oak
9.	7" Hackberry
10.	27" Live Oak
11.	11" Live Oak
12.	6" Live Oak
13.	11 1/2" Hackberry






CRZ ————
 1/2 CRZ - - - -



- Notes:
1. If a concrete washout is to be utilized during construction add a note on the plan sheets that states that the location will be determined once construction has begun and will be properly notated on the site map at that time.
 2. All required Notices and Permits must be placed in a highly visible location onsite before the commencement of construction.
 3. All erosion and sedimentation controls (ESC) must be installed prior to any disturbance to the project site.
 4. Install silt fence accordingly for run-on diversion or offsite sediment control depending on up or down slope, facing post side on the down gradient side.
 5. All ESC used onsite must be regularly monitored and maintained as needed.
 6. Mud and or dirt tracked into the roadway must be immediately removed upon discovery.
 7. Excess materials that will be transported to an offsite location must have that location cleared by County Inspector.
 8. Loose trash and debris must be disposed of properly onsite.
 9. Contractor shall maintain and utilize dust control for the duration of the project.
 10. The Stabilized Construction Entrance shall be maintained in a condition that prevents tracking onto the public roadway on an ongoing/regular basis.
 11. Inlet protection shall be installed immediately upon inlet installation.
 12. Initiate temporary stabilization when construction ceases in a disturbed area for 14 days.
 13. Initiate permanent stabilization immediately once work has ceased and final grade has been achieved.
 14. All disturbed/bare areas will require permanent stabilization before Final Acceptance can be achieved. Avoid disturbing areas of the project that are not necessary for construction.
 15. County Inspector may request additional controls be installed onsite as needed.
 16. Temporary ESC's shall remain in place in all disturbed areas until adequate stabilization has been achieved.
 17. Contractor must remove sediment from all Storm Sewer Inlet Boxes, Lines, Pipes and Culverts before Conditional/Final Acceptance can be obtained.
 18. Travis County requires Certified SWP3 Inspectors to conduct SWP3 inspections and reporting on all projects with one acre of disturbance and larger.
 19. Permittee shall inspect all inlet protection devices as part of the weekly SWP3 report, upon receiving a forecast calling for a rain event for an extended period, modification of inlet protection should be made to prevent flooding or ponding of water if traffic or property concerns arise.
 20. A de-watering plan for the pond(s) must be approved by the County Environmental Inspector if the temporary sedimentation pond is de-watered after rainfall events. The de-watering method must minimize the discharge of suspended sediments to the greatest extent feasible by drawing water from the surface of the impoundment.




- Silt Fence Specifications**
- 1.0 Silt fence shall be provided where indicated on attached drawing.
 - 2.0 Fabric shall consist of woven polypropylene, 36" in width and fastened to hardwood posts with three (3), one inch (1") wide crown staples.
 - 3.0 Posts shall be of sound hardwood, forty eight inches (48") in length with a minimum cross section of 1.125 square inches. Softwood posts shall not be used.
 - 4.0 Posts shall be positioned vertically at a distance not to exceed ten feet (10') on center for the entire length of the silt fence.
 - 5.0 Soil shall be trenched to allow six inches (6") of the silt fence fabric to fall below grade. Posts shall be driven a minimum of eighteen inches (18") below natural grade to allow six inches (6") of material to extend into the trench. Trench shall be backfilled to original grade, leaving a minimum of six inches (6") of fabric below finish grade. If the silt fence is installed on a level site, the posts shall be positioned on the downward side. If the silt fence is installed on a slope, the posts shall be positioned on the outside of the Silt Fence.
 - 6.0 Connector/joining of silt fences shall be completed by tightly overlapping the ends of the rolls a minimum of twelve inches (12") or by overlapping the end posts and securing the two posts together tightly with plastic wire ties and/or steel baling wire.





C	Added exit from contractor staging and spoils area.	03/01/21	SLM
B	Labeled all ESC measures, const. site entry and added culvert mulch socks.	01/31/21	SLM
A	Added silt fence around CSSA and shaded areas of outside LOC.	12/06/20	SLM
REV.	DESCRIPTION	DATE	BY
Lake Travis Engineering and Inspection LLC TBPE Firm No. 10248 / 512 633 7097 2106 Bee Creek Rd Temporary Erosion and Sediment Control Plan			
Scale: 1" = 30'		DATE: 03/01/21	REV: 04
DATE: 03/01/21		SCALE:	SHEET 1 OF 1

Total Area = 4.82 Acres	209,959.2 S.F.
Impervious Cover	
Driveways and Parking	37,892.6 S.F.
Office (Former House)	2,367.9 S.F.
Sanctuary/Fellowship Hall (Former Event Center)	3,915.7 S.F.
Future Sanctuary	4,550.0 S.F.
Fire Tank Pad	400.0 S.F.
Domestic Water Tank Pad	118.8 S.F.
Total Impervious Cover	49,363.8 S.F.
Impervious %	23.5%



- Notes:
- If a concrete washout is to be utilized during construction add a note on the plan sheets that states that the location will be determined once construction has begun and will be properly notated on the site map at that time.
 - All required Notices and Permits must be placed in a highly visible location onsite before the commencement of construction.
 - All erosion and sedimentation controls (ESC) must be installed prior to any disturbance to the project site.
 - Install silt fence accordingly for run-on diversion or offsite sediment control depending on up or down slope, facing post side on the down gradient side.
 - All ESC used onsite must be regularly monitored and maintained as needed.
 - Mud and or dirt tracked into the roadway must be immediately removed upon discovery.
 - Excess materials that will be transported to an offsite location must have that location cleared by County Inspector.
 - Loose trash and debris must be disposed of properly onsite.
 - Contractor shall maintain and utilize dust control for the duration of the project.
 - The Stabilized Construction Entrance shall be maintained in a condition that prevents tracking onto the public roadway on an ongoing/regular basis.
 - Inlet protection shall be installed immediately upon inlet installation.
 - Initiate temporary stabilization when construction ceases in a disturbed area for 14 days.
 - Initiate permanent stabilization immediately once work has ceased and final grade has been achieved.
 - All disturbed/bare areas will require permanent stabilization before Final Acceptance can be achieved. Avoid disturbing areas of the project that are not necessary for construction.
 - County Inspector may request additional controls be installed onsite as needed.
 - Temporary ESC's shall remain in place in all disturbed areas until adequate stabilization has been achieved.
 - Contractor must remove sediment from all Storm Sewer Inlet Boxes, Lines, Pipes and Culverts before Conditional/Final Acceptance can be obtained.
 - Travis County requires Certified SWP3 Inspectors to conduct SWP3 inspections and reporting on all projects with one acre of disturbance and larger.
 - Permittee shall inspect all inlet protection devices as part of the weekly SWP3 report, upon receiving a forecast calling for a rain event for an extended period, modification of inlet protection should be made to prevent flooding or ponding of water if traffic or property concerns arise.
 - A de-watering plan for the pond(s) must be approved by the County Environmental Inspector if the temporary sedimentation pond is de-watered after rainfall events. The de-watering method must minimize the discharge of suspended sediments to the greatest extent feasible by drawing water from the surface of the impoundment.




Sheet 6 of 18


REV.	DESCRIPTION	DATE	BY

Lake Travis Engineering and Inspection LLC TBPE Firm No. 10248 / 512 633 7097	
2106 Bee Creek Rd Set Back Averaging Plan Plan	
Scale: 1" = 30'	SHEET NO: E FSCM NO: DWG NO: 05 REV:
Date: 05/08/20	SCALE: SHEET: 1 OF 1

Total Area = 4.82 Acres	209,959.2 S.F.
Impervious Cover	
Driveways and Parking	37,892.6 S.F.
Office (Former House)	2,367.9 S.F.
Sanctuary/Fellowship Hall (Former Event Center)	3,915.7 S.F.
Future Sanctuary	4,550.0 S.F.
Fire Tank Pad	400.0 S.F.
Domestic Water Tank Pad	118.8 S.F.
Total Impervious Cover	49,363.8 S.F.
Impervious %	23.5%



- Notes:
- If a concrete washout is to be utilized during construction add a note on the plan sheets that states that the location will be determined once construction has begun and will be properly notated on the site map at that time.
 - All required Notices and Permits must be placed in a highly visible location onsite before the commencement of construction.
 - All erosion and sedimentation controls (ESC) must be installed prior to any disturbance to the project site.
 - Install silt fence accordingly for run-on diversion or offsite sediment control depending on up or down slope, facing post side on the down gradient side.
 - All ESC used onsite must be regularly monitored and maintained as needed.
 - Mud and or dirt tracked into the roadway must be immediately removed upon discovery.
 - Excess materials that will be transported to an offsite location must have that location cleared by County Inspector.
 - Loose trash and debris must be disposed of properly onsite.
 - Contractor shall maintain and utilize dust control for the duration of the project.
 - The Stabilized Construction Entrance shall be maintained in a condition that prevents tracking onto the public roadway on an ongoing/regular basis.
 - Inlet protection shall be installed immediately upon inlet installation.
 - Initiate temporary stabilization when construction ceases in a disturbed area for 14 days.
 - Initiate permanent stabilization immediately upon work has ceased and final grade has been achieved.
 - All disturbed/bare areas will require permanent stabilization before Final Acceptance can be achieved. Avoid disturbing areas of the project that are not necessary for construction.
 - County Inspector may request additional controls be installed onsite as needed.
 - Temporary ESC's shall remain in place in all disturbed areas until adequate stabilization has been achieved.
 - Contractor must remove sediment from all Storm Sewer Inlet Boxes, Lines, Pipes and Culverts before Conditional/Final Acceptance can be obtained.
 - Travis County requires Certified SWP3 Inspectors to conduct SWP3 inspections and reporting on all projects with one acre of disturbance and larger.
 - Permittee shall inspect all inlet protection devices as part of the weekly SWP3 report, upon receiving a forecast calling for a rain event for an extended period, modification of inlet protection should be made to prevent flooding or ponding of water if traffic or property concerns arise.
 - A de-watering plan for the pond(s) must be approved by the County Environmental Inspector if the temporary sedimentation pond is de-watered after rainfall events. The de-watering method must minimize the discharge of suspended sediments to the greatest extent feasible by drawing water from the surface of the impoundment.



- Contact postinspection@traviscountytx.gov to schedule the following milestone inspections for the water quality structures with at least a 48 hour notice:
- Pre-pour of all concrete within the footprint of the WQ control or pond.
 - Placement of all rock-filled gabions/mattresses.
 - Underdrain piping PRIOR to covering with sand/bio-filtration media. *- If covered, removal of material will be required.*
 - Completion of construction.







Water Quality Calculations

Run Off Volume = (.05 + (.0085 X 23.5)) X 1.93 = 0.482 in.

Water Quality Volume (WQV) = DA X 0.482/12

Drainage Areas	Area (Acres)	WQV (Cu. Ft.)	Filtration Method	Required Area (Sq. Ft.)	Provided Area (Sq. Ft.)
DA #4	0.1693	297.1	Engineered V.S.	341.7	4067
DA #6, 7, 8, 9	1.205	2108.3	Natural V.S.	4785.8	4950
DA #11, 12	1.1062	1943.0	Natural V.S.	4410.6	7700

Required Filtration Area
 Engineered V.S. = WQV X 1.15
 Natural V.S. = WQV X 2.27




REV.	DESCRIPTION	DATE	BY
A	Added culvert inlet/outlet erosion control details.	12/06/20	SLM

Lake Travis Engineering and Inspection LLC
 TBPE Firm No. 10248 / 512 633 7097


2106 Bee Creek Rd
 Permanent Erosion and Water Quality Plan

Scale: 1" = 30'	SIZE: E	FSCM NO:	DRWG NO: 06	REV:
Date: 12/06/20	SCALE:	SHEET:	1 OF 1	


1/7 Natural Vegetative Strip Detail




2/7 12" HDPE Pipe Outlet Stabilization




3/7 Berm and Basin Erosion Projection Detail



4/7 Driveway erosion projection detail



Soil Retention Blanket Stapling Pattern up to 3:1 Slopes




Notes:


- All slope protection on this site consist of a 3:1 or flatter slope with clay soils. Disturbed soils to be covered with Class 1, Type A soil retention blankets over seeded soil.
- Minimum combination of existing and imported top soil for seeding is 2".
- All soil retention blanket areas, berms, engineered vegetative strips, and basins to be seeded with the Highland Lakes Watershed Ordinance Mix per table 3-4.
- Use the Year Round mix at the rates listed in table 3-4
- TX Wildflowers may be mixed in with grass seed.
- Seeded areas to be covered with grass mat and stapled 3' O.C.E.W.
- All berms should be sloped at a 3:1 or less and be compacted to 95% prior to seeding and matting.

Table 3-4 Permanent Seeding for Burnet, Travis, and Llano Counties

Dates	Climate	Species (lb/ac)	
Year Round	Permanent Cool/Warm Season (Native Species)	Purple three-awn (Aristida purpurea)	1.4
		Sideoats grama (Bouteloua curtipendula)	2.0
		Silver chustem (Bothriochloa lagroides)	6.0
		Buffalograss (Buchloe dactyloides)	1.4
		Canadian wildrye (Elymus Canadensis)	1.4
		Engelmann's daisy (Engelmannia pinnatifida)	0.6
		Green sprangletop (Leptochloa dubia)	2.6
		Mexican hat (Ratibida columnifera)	1.0
		Little bluestem (Schizachyrium scoparium)	1.8
		Indiangrass (Sorghastrum nutans)	1.8
		Texas Wintergrass (Nassella leucotricha)	15.0
		Total	
Mar 30 to Oct 1	Permanent Warm Season	Bermuda (Cynodon dactylon)(hulled)	45.0
Oct 1 to Mar 30	Permanent Cool/Warm Season	Bermuda (Cynodon dactylon) (unhulled)	70.0
		Cereal Rye (Secale cereale)	90.0
		Total	160.0




Note: depth of discharge is 4" and slope is .09. Shear equates to 1.68 PSF < 3 PSF. Discharge to grass vegetation is acceptable.



REV.	A	Added LCRA HLWO seed schedule.	01/31/21	SLM
		DESCRIPTION	DATE	BY
		Lake Travis Engineering and Inspection LLC TBPE Firm No. 10248 / 512 633 7097		
		Spirit in the Hills Lutheran Church 2106 Bee Creek Rd Water Quality and Restoration Details		
Scale:	1/2" = 1'-0"	REV.	07	REV.
Date:	01/31/21	SCALE:	1/2" = 1'-0"	SHEET

Total Area = 4.82 Acres	209,959.2 S.F.
Impervious Cover	
Driveways and Parking	37,892.6 S.F.
Office (Former House)	2,367.9 S.F.
Sanctuary/Fellowship Hall (Former Event Center)	3,915.7 S.F.
Future Sanctuary	4,550.0 S.F.
Fire Tank Pad	400.0 S.F.
Domestic Water Tank Pad	118.8 S.F.
Total Impervious Cover	49,363.8 S.F.
Impervious %	23.5%




- Erosion Control Notes:
- All slope protection on this site consist of a 3:1 or flatter slope with clay soils. Disturbed soils to be covered with Class 1, Type A grass/soil retention blankets over seeded soil.
 - Minimum combination of existing and imported top soil for seeding is 2".
 - All grass blanket areas, berms, engineered vegetative strips, and basins to be seeded with DOT Permanent Rural Seed Mix for the Austin area. See mix below.
 - Apply at a mixed rate of 7 Pounds/Acre.
 - TX Wildflowers may be mixed in with grass seed.
 - Seeded areas to be covered with grass mat and stapled 3' O.C.E.W.
 - All berms should be sloped at a 3:1 or less and be compacted to 95% prior to seeding and matting.
 - See details on page 7 – Water Quality and Restoration Details.




Green Sprangletop	0.3
Bermudagrass	0.9
Sideoats Grama (Haskell)	2.7
Little Bluestem (Native)	1.0
Blue Grama (Hachita)	0.9
Illinois Bundleflower	1.0

Lot 10

Lot 3

Lot 5



-  Engineered V.S. – Provide top soil, seed and soil retention blankets per details on drawing 7 on basin, berms and disturbed soil.
-  Natural Well Established V.S.
-  Provide top soil, seed and soil retention blankets per details on drawing 7 on basin, berms and disturbed soil.


- Notes:
- Initiate permanent stabilization immediately once work has ceased and final grade has been achieved in any given area.
 - The final stabilization/revegetation efforts shall be in accordance with the approved Restoration Plan details and specifications.
 - All 3:1 slopes or steeper require soil retention blanket (SRB).
 - The contractor is responsible for providing adequate watering/irrigation to achieve the permanent stabilization requirements in all disturbed/revegetated areas before final acceptance for this project can be obtained.
 - All disturbed/bare areas will require permanent stabilization before Final Acceptance can be achieved. Avoid disturbing areas of the project that are not necessary for construction.
 - Any disturbed area(s) not indicated to be restored on the restoration plan requires the same efforts as those indicated.
 - All disturbed areas must meet the requirement for permanent stabilization.
 - The Notice of Termination (NOT) for this project shall not be submitted until the Travis County Environmental Inspector approves clearance.

Note: depth of discharge is 4" and slope is .09. Shear equates to 1.68 PSF < 3 PSF. Discharge to grass vegetation is acceptable.


Un-named tributary approximately 2,915' from the edge of the 100 year FEMA floodplain for Colorado River / Lake Travis

Bee Creek Road R.O.W

SWP3 Sign and Permit Posting Location




REV.	DESCRIPTION	DATE	BY
A	Removed contour lines and added shading for restoration areas.	12/06/20	SLM
Lake Travis Engineering and Inspection LLC TBPE Firm No. 10248 / 512 633 7097 2106 Bee Creek Rd Stabilization/Restoration Plan			
Scale: 1" = 30'	SHEET	DWG NO	REV
Date: 12/06/20	SCALE	08	1 OF 1




1
09 Concrete Driveway Approach from Street Details


Type II City of Austin Driveway Approach per Standard No. 4335-2
6" thick, 3000 psi concrete with #4 bars 16" O.C.E.W.




25'-0" Cross Section



2
09 Asphalt Main Driveway Paving Cross Section



3
09 Asphalt Parking Paving Cross Section



4
09 Concrete Bridge Cross Section

- Concrete Notes and Specifications
- All concrete construction shall meet the requirements of the American Concrete Institute (ACI) building code requirements for reinforced concrete (ACI 318-05).
 - All organics must be removed and soil must be compacted to 95% compaction with heavy equipment in maximum of 12" lifts with water added between lifts. All fill to be select fill with no organic or clay content.
 - Reinforcing bars shall be grade 60 deformed bars and meet the requirements of ASTM A615. Splice laps, hooks and bends should meet the schedules on this sheet. Concrete cover shall be a minimum of 1 1/2" for #4 and smaller bars and a minimum of 2" for #5 and larger bars. All reinforcing bars to be placed in middle of concrete thickness unless otherwise specified.
 - All reinforcement bars should be spaced off of soil with permanent plastic chairs or concrete blocks. Rebar shall not be permitted to come in contact with soil.
 - Contractor shall verify finishes prior to placing concrete. All inside finishes are to be hard troweled. Exterior finished to have a light broom finish.
 - Concrete for all floor slabs shall have a compressive strength of 3500 PSI and exterior paving to have a compressive strength of 3000 PSI. Curbs and flumes to have a compressive strength of 2500 psi. Slump to be no greater than 5" (4" target slump).
 - All interior concrete which may be subject to tile or other flooring must have 10 mil poly applied to compacted soil prior to the installation of reinforcement steel and concrete.

- Asphalt Concrete Notes and Specifications:
- All disturbed soil to be compacted to 95% compaction in no more than 12" lifts.
 - Crushed/decomposed rock base to be compacted in no more than 6" lifts to 95% compaction.
 - Paving for upper parking area and driveway past buildings to be a minimum of 5" base to be covered by 1.5" of Class A hot asphalt concrete
 - Paving for main drive ways to be minimum of 8" base covered with 1.5" of class A hot asphalt concrete.
 - A prime/tack coat shall be applied ahead of the asphalt concrete with a bituminous material temperature between 140 and 180 deg. F.
 - Asphalt Concrete to be placed a minimum temperature of 250 deg. F.
 - Asphalt to be have initial compaction with a steel drum roller with a minimum of 225 deg. F temperature.
 - Intermediate passes may be with a rubber tired roller, with final pass with a steel drum roller.
 - All fire lane areas with more than 10% of grade shall have a light chip seal coat applied over asphalt for vehicle traction.

- Striping
- Parking spaces to be lined for 8.0' wide by 18' long spaces with yellow stripes.
 - ADA Accessibility paths between spaces to be a minimum of 5' wide and to be cross lined with blue stripes 12" O.C. at a diagonal.
 - All fire lanes to be either striped or signed per local fire code requirements.

Table 7 - Tension Development and Lap Splice Lengths for Bars in Walls, Slabs and Footings (ACI 25.4.2.3)

$f_c = 3,000 \text{ psi}$

Bar Size	Lap Class	Concrete Cover = 0.75 in.				Concrete Cover = 1.50 in.				Concrete Cover = 2.00 in.				Concrete Cover = 3.00 in.				
		Uncoated		Epoxy-Coated		Uncoated		Epoxy-Coated		Uncoated		Epoxy-Coated		Uncoated		Epoxy-Coated		
		Top	Other	Top	Other	Top	Other	Top	Other	Top	Other	Top	Other	Top	Other	Top	Other	
#3	A	13	17	17	15	13	17	15	13	17	15	13	17	15	13	17	15	13
	B	17	13	22	20	17	13	22	20	17	13	22	20	17	13	22	20	17
#4	A	22	24	24	21	19	23	21	19	23	21	19	23	21	19	23	21	19
	B	28	22	37	35	28	22	37	35	28	22	37	35	28	22	37	35	28
#5	A	32	34	34	31	29	33	31	29	33	31	29	33	31	29	33	31	29
	B	41	32	44	41	38	42	40	38	42	40	38	42	40	38	42	40	38
#6	A	43	45	45	42	40	44	42	40	44	42	40	44	42	40	44	42	40
	B	56	43	73	64	54	59	54	51	57	54	51	57	54	51	57	54	51
#7	A	60	63	63	60	57	61	59	57	61	59	57	61	59	57	61	59	57
	B	80	60	117	104	75	83	72	64	89	78	64	95	84	69	98	84	69
#8	A	66	66	112	99	64	70	62	43	33	56	50	43	33	56	50	43	33
	B	111	86	146	126	70	84	61	30	26	40	30	26	40	30	26	40	30
#9	A	104	80	136	120	66	71	63	41	30	41	35	27	20	33	26	20	17
	B	150	104	186	166	86	91	79	52	36	52	41	30	20	33	26	20	17
#10	A	120	96	135	118	74	81	69	44	33	46	39	30	22	33	26	20	17
	B	162	125	212	187	105	113	101	66	46	66	51	39	27	35	28	22	19
#11	A	140	113	151	133	82	74	78	51	39	61	52	41	31	41	33	26	20
	B	190	146	248	219	125	97	104	64	45	102	79	54	38	61	45	33	26

Table - Tension Development and Lap Splice Lengths for Bars in Walls, Slabs and Footings (ACI 25.4.2.3)

$f_c = 4,000 \text{ psi}$


Bar Size	Lap Class	Concrete Cover = 0.75 in.				Concrete Cover = 1.50 in.				Concrete Cover = 2.00 in.				Concrete Cover = 3.00 in.				
		Uncoated		Epoxy-Coated		Uncoated		Epoxy-Coated		Uncoated		Epoxy-Coated		Uncoated		Epoxy-Coated		
		Top	Other	Top	Other	Top	Other	Top	Other	Top	Other	Top	Other	Top	Other	Top	Other	
#3	A	12	12	15	13	12	12	15	13	12	12	15	13	12	12	15	13	12
	B	15	12	19	17	15	12	19	17	15	12	19	17	15	12	19	17	15
#4	A	19	19	24	22	19	19	24	22	19	19	24	22	19	19	24	22	19
	B	26	19	32	28	20	15	26	22	20	15	26	22	20	15	26	22	20
#5	A	26	26	32	30	26	26	32	30	26	26	32	30	26	26	32	30	26
	B	36	26	47	41	24	19	33	28	24	19	33	28	24	19	33	28	24
#6	A	31	31	38	35	31	31	38	35	31	31	38	35	31	31	38	35	31
	B	43	31	51	45	32	25	51	44	32	25	51	44	32	25	51	44	32
#7	A	40	40	48	45	40	40	48	45	40	40	48	45	40	40	48	45	40
	B	56	40	66	58	42	33	66	57	42	33	66	57	42	33	66	57	42
#8	A	44	44	54	50	44	44	54	50	44	44	54	50	44	44	54	50	44
	B	60	44	74	64	46	36	74	64	46	36	74	64	46	36	74	64	46
#9	A	50	50	60	56	50	50	60	56	50	50	60	56	50	50	60	56	50
	B	68	50	84	74	54	41	84	74	54	41	84	74	54	41	84	74	54
#10	A	56	56	68	64	56	56	68	64	56	56	68	64	56	56	68	64	56
	B	76	56	96	84	60	46	96	84	60	46	96	84	60	46	96	84	60
#11	A	60	60	72	68	60	60	72	68	60	60	72	68	60	60	72	68	60
	B	84	60	108	96	70	54	108	96	70	54	108	96	70	54	108	96	70

- Notes:
- Tabulated values are based on a minimum yield strength of 60,000 psi and normal-weight concrete. Lengths are in inches.
 - Tension development lengths and tension lap splice lengths are calculated per ACI 318-14, Sections 25.4.2.3 and 25.5.1, respectively, with bar sizes limited to #3 through #11.
 - When the variable c_d from ACI 25.4.2.3 was calculated, it was assumed that concrete cover controlled. That is, c-c. spacing was assumed to be greater than $1.0 d_b$ plus twice the concrete cover.
 - Lap splice lengths (minimum of 12 inches) are multiples of tension development lengths: Class A = $1.0 d_b$ and Class B = $1.3 d_b$ (ACI 318 25.5.1). When determining the lap splice length, d_b is calculated without the 12-inch minimum of ACI 25.4.2.1.
 - Top bars are horizontal bars with more than 12 inches of concrete cast below the bars.
 - For epoxy-coated bars, if the c-c. spacing is at least $7.0 d_b$ and the concrete cover is at least $3.0 d_b$, then lengths may be multiplied by 0.918 (for top bars) or 0.8 (for other bars).
 - For Grade 75 reinforcing bars, multiply the tabulated values by 1.25. For Grade 80 reinforcing bars, multiply the tabulated values by 1.33.
 - For lightweight concrete, divide the tabulated values by 0.75.


Use Lap Class B and Case 1
Based on Grade 60 steel and ACI 318-02. Splice lap lengths in inches.

Standard Hook and Bend Dimensions


Bar Size	D (in.)	180° Hooks		90° Hooks	
		A or G	J	A or G	J
#3 (#10)	2-1/4"	5"	3"	6"	3"
#4 (#13)	3"	6"	4"	8"	4"
#5 (#16)	3-3/4"	7"	5"	10"	5"
#6 (#19)	4-1/2"	8"	6"	1'-0"	6"
#7 (#22)	5-1/4"	10"	7"	1'-2"	7"
#8 (#25)	6"	11"	8"	1'-4"	8"
#9 (#29)	6-1/2"	1'-3"	11-3/4"	1'-7"	9"
#10 (#32)	10-3/4"	1'-5"	1'-1-1/4"	1'-10"	10"
#11 (#36)	12"	1'-7"	1'-2-3/4"	2'-0"	11"
#14 (#43)	18-1/4"	2'-3"	1'-9-3/4"	2'-7"	14"
#18 (#57)	24"	3'-0"	2'-4-1/2"	3'-5"	18"




Based on Grade 60 steel and ACI 318-02




REV.	DESCRIPTION	DATE	BY
	Lake Travis Engineering and Inspection LLC TBPE Firm No. 10248 / 512 633 7097		
	Spirit in the Hills Lutheran Church 2106 Bee Creek Rd Water Quality and Restoration Details		
Scale: 1/2" = 1'-0"	DATE: 09/19/21	SHEET: 07	REV: 1 OF 1



2 PRE-DEVELOPED DRAINAGE MAP Scale: 1:60



3 DEVELOPED DRAINAGE MAP Scale: 1:60



1 OFFSITE DRAINAGE MAP Scale: 1:200

AUSTIN CIVIL ENGINEERING, INC.

TYPE FIRM # E-001018
9901 B MENCHACA RD, SUITE 220
AUSTIN, TX 78748
PH: (512) 306-0018

SPIRIT IN THE HILLS CHURCH

2106 BEE CREEK ROAD
SPICEWOOD, TRAVIS COUNTY, TEXAS

10 OF 10


REVISIONS

REV. DATE	DESCRIPTION	APPROVED BY


JOB: 19-048 DATE: 10/5/20
 CAD: DA/MM CHKD BY: _____
 ENGINEER: HS CHKD BY: _____
 SCALE: _____

SITE CIVIL PLAN

10 OF 10



AUSTIN CIVIL ENGINEERING, INC.
 ENGINEERING FIRM # F-001018
 9501 B MENCHACA RD, SUITE 220
 AUSTIN, TX 78748
 PH: (512) 306-0018





SPIRIT IN THE HILLS CHURCH
 2106 BEE CREEK ROAD
 SPICEWOOD, TRAVIS COUNTY, TEXAS

REV. DATE	REVISIONS DESCRIPTION	APPROVED BY


JOB: 19-048 DATE: 10/5/20
 CAD: DMM CHK'D BY: [Signature]
 ENGINEER: HS CHK'D BY: [Signature]
 SCALE: 1" = 30'

GRADING PLAN


SITE CIVIL PLAN
 OF 11













6" CONC. 3000 PSI W/ # 3 REBAR @ 18" O.C.E.W. EXPANSION JOINTS AT 40' O.C.



1 CONCRETE VALLEY GUTTER
 Scale: NTS



2 STAND UP CURB
 Scale: NTS



Culvert Report




Hydrowall Express Extension for Autodesk® Civil 3D® by Autodesk, Inc. Monday, Oct 5 2020

(4) 48" CMP CULVERT


Invert Elev Dn (ft)	= 785.50	Calculations	= 0.00
Pipe Length (ft)	= 42.97	Qmin (cfs)	= 527.00
Slope (%)	= 2.33	Qmax (cfs)	= 0.00
Invert Elev Up (ft)	= 786.50	Tailwater Elev (ft)	= 0.00
Rise (in)	= 48.0		
Shape	= Circular	Highlighted	
Span (in)	= 48.0	Qtotal (cfs)	= 527.00
No. Barrels	= 4	Qpipe (cfs)	= 474.74
n-Value	= 0.024	Qovertop (cfs)	= 52.26
Culvert Type	= Circular Culvert	Veloc Dn (ft/s)	= 10.76
Culvert Entrance	= Smooth tapered inlet throat	Veloc Up (ft/s)	= 10.74
Coeff. K _{M,c,Y,k}	= 0.534, 0.555, 0.0196, 0.9, 0.2	HGL Dn (ft)	= 788.78
		HGL Up (ft)	= 789.79
		Hw Elev (ft)	= 791.80
		Hw/D (ft)	= 1.33
		Flow Regime	= Inlet Control

Embankment

Top Elevation (ft)	= 791.00
Top Width (ft)	= 30.00
Crest Width (ft)	= 24.00



AUSTIN CIVIL ENGINEERING, INC.
TYPE FIRM # F-001018
9501 B MENCHACA RD, SUITE 220
AUSTIN, TX 78748
PH: (512) 306-0018



SPIRIT IN THE HILLS CHURCH
2106 BEE CREEK ROAD
SPICEWOOD, TRAVIS COUNTY, TEXAS

REV.	DATE	DESCRIPTION	APPROVED BY

JOB: 19-048 DATE: 10/5/20
CAD: DMM CHK'D BY:
ENGINEER: HS CHK'D BY:
SCALE:

CULVERT & CREEK SECTIONS

SITE CIVIL PLAN
12
OF

POA "C"

Spirit of the Hills - South Pond for Church Area

Detention Pond	Storage	Cumulative	Cumulative
Stage (ft)	Area (sf)	Area (ac)	ac-ft
801.50	8.0	0.0002	0
803.00	16.0	0.0004	18
803.50	2769.0	0.0636	1,705
804.00	4096.0	0.0940	2,152
804.50	4517.0	0.1037	2,363
805.00	4938.0	0.1134	2,528
805.50	5173.0	0.1188	2,645
806.00	5408.0	0.1242	2,645



Spirit of the Hills - South Pond for Church Area

Summary Routing table (Stage / Storage / Discharge)					POA C
Storm Event	Developed flows (to det. pond) Q - cfs	Dev (Routed) Qa - cfs	Pond Elevation Stage ft	Storage	CFT
2-yr	5.48	2.52	803.75	1,429	0.0
10-yr	9.86	6.05	804.13	2,914	0.0
25-yr	12.30	7.27	804.37	3,947	0.0
100-yr	16.35	8.89	804.78	5,833	0.0

Spirit of the Hills - South Pond for Church Area
DETENTION POND OUTFLOW Structure

Orifice		Orifice		Weir		Total Flow	
Dia (in)	Area (sq ft)	Dia (in)	Area (sq ft)	L (ft)	C=3.0	Q (cfs)	Q (cfs)
8.000	0.667	15.000	1.250	1.00		0.00	0.00
0.6	0.35	0.6	1.23	1.00		0.84	0.84
801.50	flowline	803.80	flowline	999.00	flowline	1.19	1.19


elevation	H	Q (cfs)	H	Q (cfs)	H	Q (cfs)	Q (cfs)	elevation
801.50	0.00	0.00	0.00	0.00	0.00	0.00	0.00	801.50
801.75	0.25	0.84	0.00	0.00	0.00	0.00	0.84	801.75
802.00	0.50	1.19	0.00	0.00	0.00	0.00	1.19	802.00
802.25	0.75	1.46	0.00	0.00	0.00	0.00	1.46	802.25
802.50	1.00	1.68	0.00	0.00	0.00	0.00	1.68	802.50
802.75	1.25	1.88	0.00	0.00	0.00	0.00	1.88	802.75
803.00	1.50	2.06	0.00	0.00	0.00	0.00	2.06	803.00
803.25	1.75	2.22	0.00	0.00	0.00	0.00	2.22	803.25
803.50	2.00	2.38	0.00	0.00	0.00	0.00	2.38	803.50
803.75	2.25	2.52	0.00	0.00	0.00	0.00	2.52	803.75
804.00	2.50	2.66	0.20	2.64	0.00	0.00	5.30	804.00
804.25	2.75	2.79	0.45	3.96	0.00	0.00	6.75	804.25
804.50	3.00	2.91	0.70	4.94	0.00	0.00	7.85	804.50
804.75	3.25	3.03	0.95	5.76	0.00	0.00	8.79	804.75
805.00	3.50	3.14	1.20	6.47	0.00	0.00	9.62	805.00



	(18")	(20")	(22")	(24")	(27")
A	(18")	(20")	(22")	(24")	(27")
B	(30")	(32")	(34")	(42")	(51")
D	(6")	(8")	(10")	(12")	(15")
L	(24")	(24")	(30")	(36")	(48")



1 HEDWALL DETAIL

Scale: NTS



2B 10" PVC W/ 9.5" RESTRICTOR PLATE

Scale: NTS




4 CONCRETE FLUME

Scale: NTS

ENGINEERED FILL SOILS PLACED TO CREATE AN EARTHEN BERM SHOULD CONSIST OF CLAYEY SOILS WITH A PLASTICITY INDEX (PI) LESS THAN 40, AT LEAST 70% PASSING THE NO. 200 SIEVE, A MAXIMUM GRAVEL CONTENT (PERCENTAGE RETAINED ON NO. 4 SIEVE) OF 25%, AND A MAXIMUM PARTICLE SIZE OF 1". ENGINEERED FILL SOILS SHOULD BE PLACED IN RELATIVELY HORIZONTAL LIFTS AND BENCHED INTO UNDISTURBED SOILS ON EITHER SIDE OF THE BERM. THE ENGINEERED FILL SHALL BE PLACED IN LIFTS NO GREATER THAN 8" IN THICKNESS AND SHALL BE COMPACTED TO AT LEAST 95% OF THE MAXIMUM DRY DENSITY AS DETERMINED BY THE STANDARD PROCTOR TEST (ASTM D698). THE MOISTURE OF THE ENGINEERED FILL SOILS SHALL BE MAINTAINED BETWEEN THE OPTIMUM MOISTURE CONTENT TO 4% ABOVE THE OPTIMUM MOISTURE CONTENT VALUE."



THIS PLAN FOR DETENTION DESIGN ONLY.



3 POND CROSS SECTION


Scale: NTS

THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. HE AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.



- LEGEND
- 1/2" ROD FOUND
 - WIRE FENCE
 - RECORD INFORMATION
 - UTILITY POLE
 - OVERHEAD UTILITY LINE(S)
 - ELECTRIC RISER
 - SEPTIC PUMP
 - CLEAN OUT
 - SEPTIC LID
 - AIR CONDITIONER
 - 600 NAIL SET FOR POINT ON LINE

AUSTIN CIVIL ENGINEERING, INC.
 TYPE FIRM # F-001018
 9801 B MENCHACA RD. SUITE 220
 AUSTIN, TX 78748
 PH: (512) 306-0018



SPIRIT IN THE HILLS CHURCH
 2106 BEE CREEK ROAD
 SPICEWOOD, TRAVIS COUNTY, TEXAS








REV. DATE	DESCRIPTION	APPROVED BY

JOB: 19-048 DATE: 10/5/20
 CAD: DAW/CHK'D BY:
 ENGINEER: HS CHK'D BY:
 SCALE:

SOUTH POND
 13 OF

**Spirit of the Hills - North Pond
DETENTION POND OUTFLOW Structure**

# pipes	4	input inches	L (ft) =	0.00				
Diag - in	3.000		L (ft) =	0.00				
Diag - ft	0.250							
Orifice	0.6	Weir	C=3.0	Weir	C=3.0	Total		
A sft =	0.196	L (ft) =	835.80	L (ft) =	999.00	Flow		
835.00	flowline	835.80	flowline	999.00	flowline			
Orifice H	H	Q (cfs)	H	Q (cfs)	H	Q (cfs)	elevation	
note orifice flat (to top of pipe)								
835.00	0.00	0.00	0.00	0.00	0.00	0.00	835.00	
835.05	0.05	0.21	0.00	0.00	0.00	0.21	835.05	
835.25	0.25	0.47	0.00	0.00	0.00	0.47	835.25	
835.30	0.30	0.52	0.00	0.00	0.00	0.52	835.30	
835.35	0.35	0.56	0.00	0.00	0.00	0.56	835.35	
835.40	0.40	0.60	0.00	0.00	0.00	0.60	835.40	
835.45	0.45	0.63	0.00	0.00	0.00	0.63	835.45	
835.50	0.50	0.67	0.00	0.00	0.00	0.67	835.50	
835.55	0.55	0.70	0.00	0.00	0.00	0.70	835.55	
835.60	0.60	0.73	0.00	0.00	0.00	0.73	835.60	
835.65	0.65	0.76	0.00	0.00	0.00	0.76	835.65	
835.70	0.70	0.79	0.00	0.00	0.00	0.79	835.70	
835.75	0.75	0.82	0.00	0.00	0.00	0.82	835.75	
835.80	0.80	0.85	0.00	0.00	0.00	0.85	835.80	
835.85	0.85	0.87	0.05	0.10	0.00	0.97	835.85	
835.90	0.90	0.90	0.10	0.28	0.00	1.18	835.90	
835.95	0.95	0.92	0.15	0.52	0.00	1.44	835.95	
836.00	1.00	0.95	0.20	0.80	0.00	1.75	836.00	
836.05	1.05	0.97	0.25	1.12	0.00	2.09	836.05	
836.10	1.10	0.99	0.30	1.48	0.00	2.47	836.10	
836.15	1.15	1.01	0.35	1.86	0.00	2.88	836.15	
836.20	1.20	1.04	0.40	2.28	0.00	3.31	836.20	
836.25	1.25	1.06	0.45	2.72	0.00	3.77	836.25	




THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. HE AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

ENGINEERED FILL SOILS PLACED TO CREATE AN EARTHEN BERM SHOULD CONSIST OF CLAYEY SOILS WITH A PLASTICITY INDEX (PI) LESS THAN 40, AT LEAST 70% PASSING THE NO. 200 SIEVE, A MAXIMUM GRAVEL CONTENT (PERCENTAGE RETAINED ON NO. 4 SIEVE) OF 25%, AND A MAXIMUM PARTICLE SIZE OF 1". ENGINEERED FILL SOILS SHOULD BE PLACED IN RELATIVELY HORIZONTAL LIFTS AND BENCHED INTO UNDISTURBED SOILS ON EITHER SIDE OF THE BERM. THE ENGINEERED FILL SHALL BE PLACED IN LIFTS NO GREATER THAN 8" IN THICKNESS AND SHALL BE COMPACTED TO AT LEAST 95% OF THE MAXIMUM DRY DENSITY AS DETERMINED BY THE STANDARD PROCTOR TEST (ASTM D698). THE MOISTURE OF THE ENGINEERED FILL SOILS SHALL BE MAINTAINED BETWEEN THE OPTIMUM MOISTURE CONTENT TO 4% ABOVE THE OPTIMUM MOISTURE CONTENT VALUE."

THIS PLAN FOR DETENTION DESIGN ONLY.

AUSTIN CIVIL ENGINEERING, INC.
 TYPE FIRM # F-001018
 9501 B MENCHACA RD, SUITE 220
 AUSTIN, TX 78748
 PH: (512) 306-0018






SPIRIT IN THE HILLS CHURCH
 2106 BEE CREEK ROAD
 SPICEWOOD, TRAVIS COUNTY, TEXAS

REV. DATE	DESCRIPTION	APPROVED BY


JOB: 19-048 DATE: 10/5/20
 CAD: DMM CHK'D BY:
 ENGINEER: HS CHK'D BY:
 SCALE:

NORTH POND

SITE CIVIL PLAN
14
 OF



AUSTIN CIVIL ENGINEERING, INC.
 LICENSE # F-001018
 9501 B MENCHACA RD, SUITE 220
 AUSTIN, TX 78748
 PH: (512) 306-0018




SPIRIT IN THE HILLS CHURCH
 2106 BEE CREEK ROAD
 SPICEWOOD, TRAVIS COUNTY, TEXAS

REV. DATE	REVISIONS DESCRIPTION	APPROVED BY

JOB: 19-048 DATE: 10/5/20
 CAD: DMM CHKD BY:
 ENGINEER: HS CHKD BY:
 SCALE:


TRAFFIC CONTROL PLAN

SITE CIVIL PLAN
15
 OF



Silt Fence Specifications

- 1.0 Silt fence shall be provided where indicated on attached drawing.
- 2.0 Fabric shall consist of woven polypropylene, 36" in width and fastened to hardwood posts with three (3), one inch (1") wide crown staples.
- 3.0 Posts shall be of sound hardwood, forty eight inches (48") in length with a minimum cross section of 1.125 square inches. Softwood posts shall not be used.
- 4.0 Posts shall be positioned vertically at a distance not to exceed ten feet (10') on center for the entire length of the silt fence.
- 5.0 Soil shall be trenched to allow six inches (6") of the silt fence fabric to fall below grade. Posts shall be driven a minimum of eighteen inches (18") below natural grade to allow six inches (6") of material to extend into the trench. Trench shall be backfilled to original grade, leaving a minimum of six inches (6") of fabric below finish grade. If the silt fence is installed on a slope, the posts shall be positioned on the downward side. If the silt fence is installed on a level site, the posts shall be installed to the outside of the Silt Fence.
- 6.0 Connection/joining of silt fences shall be completed by tightly overlapping the ends of the rolls a minimum of twelve inches (12") or by overlapping the end posts and securing the two posts together tightly with plastic wire ties and/or steel bailing wire.



Septic System Calculations and Notes

Existing System Specifications:
 1500 Gallon 2 Compartment Holding Tank with 500 Gallon Pre Treatment and 1000 Gallon Dosing.
 AA600W-4075 Treatment Tank with 400 Gallon Pre Treatment, 694 Gallon Aeration, 262 Gallon Clarifier and 750 Gallon Pump Tank.
 (2) K-Rain 11003 RCW Sprinkler Heads with #3 nozzle 28" Radius
 Soil Class IV - 1' of Silty Clay and Clay Soils over limestone. Limestone extends down to a depth over 146 feet per water well drilling report dated 04/22/16. Classifications of limestone vary from Tan to White Tan to Gray Tan down to a drilling depth of 146' at what point other types of soil are found.
 Water Savings Devices Installed
 Original system design attached.


Maximum Church Occupancy = 139 Persons (Max seats of 129 + 10 worship assistants)
 Existing Home/New Church Office - To be used only as an office building, not a residence with 2 employees.
 Worship Daily Usage Rate = 4 Gal/Day/Person (Seat) (Per 285.91 Table III Wastewater Usage Rate - Theaters)
 Only one worship service per week.
 Other 5 days, Occupancy is only 2 employees for office use = 8 Gal/Day/Employee (Per 285.91 Table III)
 Q(max) = 4 X 139 X 1 day/week + 8 X 2 X 5 days/week = 636 gallons/week.

Showers and washing machines not to be used.
 There is no known rainwater collection system.
 1500 Gallon Holding Tank more than adequate for 2 day effluent holding.
 Tank can be emptied over 2 day period = 318 Gal per day.
 Q(2 day average) = 318 Gal per day.

Required Spray Area (A)
 A = Q/R
 R = 0.64 Gal/SF/Day
 A(Required) = 318 / 0.64 = 4968.8 S.F.

Existing heads located in proposed detention pond area and have to be relocated.
 28" Radius Sprinkler Head with 180 deg spray = 1231.5 S.F.
 28" Radius Sprinkler Head with 180 deg spray overlapping = 753 S.F.
 22" Radius Sprinkler Head with 180 deg spray = 760.3 S.F.
 (3) 28" Radius and (1) 22" Radius 180 deg heads = 5040.1 S.F. > 4968.8 S.F. required.

Flow Requirements
 5 Hour Max Run Time - Use 2 Hours for calculations for factor of safety
 Required Flow = 318 gallons/2 hours/60 min/hour = 2.7 GPM
 Adding losses for 300 Ft of 1 1/2" PVC pipe at 10 GPM (1.6 Ft/100 Ft) and 23' of elevation change = 27.8 Ft of head loss.
 Add delivery pressure of 25 psi (57.8 Ft) and total head on pump = 85.6 Ft
 Using Sta-Rite 20DOM05121 10 GPM pump curve total expected flow = 13 GPM > 2.7 GPM, OK
 K Rain 1100E-RCS head flow 2.3 GPM each at 25 psi and are good for a 29" radius. 4 heads X 2.3 = 9.2 GPM < 13 GPM, OK





K Rain 11003-RCW ProPlus Low Angle Heads

Flow Requirements
 5 Hour Max Run Time - Use 2 Hours for calculations for factor of safety
 Required Flow = 318 gallons/2 hours/60 min/hour = 2.7 GPM
 Adding losses for 300 Ft of 1 1/2" PVC pipe at 10 GPM (1.6 Ft/100 Ft) and 23' of elevation change = 27.8 Ft of head loss.
 Add delivery pressure of 25 psi (57.8 Ft) and total head on pump = 85.6 Ft
 Using Sta-Rite 20DOM05121 10 GPM pump curve total expected flow = 13 GPM > 2.7 GPM, OK
 K Rain 1100E-RCS head flow 2.3 GPM each at 25 psi and are good for a 29" radius. 4 heads X 2.3 = 9.2 GPM < 13 GPM, OK

Low Angle Nozzles (Green)

Nozzle	PSI	Radius	Flow
1	25	25	1.1
	20	23	1.0
	15	20	0.9
3	25	29	2.3
	20	25	2.0
	15	21	1.6
4	25	30	3.7
	20	27	3.2
	15	22	2.7
6	30	33	5.8
	25	31	5.0
	20	27	4.3
10	15	20	3.6
	10	12	2.5

* Little to no break-up coverage



REV.	DESCRIPTION	DATE	BY

Lake Travis Engineering and Inspection LLC
 TBPE Firm No. 10248 / 512 633 7097


2106 Bee Creek Rd
 Septic Modifications Plan

Scale: 1" = 30'

Date: 05/07/20

SHEET 1 OF 1

350'
71" Grade EL




- Project Notes:
1. Type II driveway details found on Proposed Site Plan sheet 03 and Paving details sheet 09.
 2. Temporary construction traffic control plan is shown on the Traffic Control Plan sheet 15.
 3. From the Austin Transportation Criteria Manual, Table 5-3.1 (K), the required spacing between road and driveway for Minor Collector is 80 Ft.

Desired Minimum Sightline Calculations
Per AASHTO Equation 3-1 the braking distance/sight lines were calculated:


$$d_{brake} = 1.075 V^2/a \quad \text{AASHTO Equation 3-1}$$

Where
 $V = 45 \text{ MPH (Posted Speed)}$
 $a = 11.2 \text{ ft/s}^2 \quad \text{Listed as recommendation--AASHTO Chapter 3}$
 $d_{brake} = 194.4 \text{ Ft.}$


- Left Sightline with Proposed Driveway Location – Vehicle Existing Driveway
- Right Sightline with Proposed Driveway Location – Vehicle Existing Driveway
- - - Left Sightline with Proposed Driveway Location – Vehicle on Bee Creek Rd. with object in road.
- - - Right Sightline with Proposed Driveway Location – Vehicle on Bee Creek Rd. with object in road.



Plan View



Elevation/Contour View



REV.	DESCRIPTION	DATE	BY

Lake Travis Engineering and Inspection LLC
 TBPE Firm No. 10248 / 512 633 7097
 2106 Bee Creek Rd
 Site Entrance Sight Lines

Scale: 1in = 20ft. 0in.
 Date: 09/19/21